BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work:-Asphalting to 12th A Cross and other roads in Yelahanka New Town in ward No:04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	KSRRB 300-1:Earthwork excavtion by manual means in ordinary soil involving an average horizontal throw upto 2 Meters and an average lift upto 0.5m excavated surface leveled and sides neatly dressed the disposed earth to be levelled neatly after breaking of clods complete as per specifications and complete as per specifications with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	189.45	65.88	Rupees sixty five and paise eighty eight only
2	KSRRB M400-17.Providing, laying, spreading and compacting graded stones aggregate to Wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specification. MORTH Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	157.95	1121.04	Rupees one thousand one hundrod twenty one and paise four only
3	KSRRB M500-6: providing and applying primer coat with bitumen emulsion on prepared surface of granular base of low porosity such as WBM and WMM including clearing of road surface and spraying primer at the rate of 1.35 kg / sqm using mechanical means complete as per specifications. MORTH specification NO. 502, No. 175/ Item No. 21.6/ PWD SR 2013-14	Sqm	631.80	44.28	Rupees forty four and paise twentye eight only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
4	KSRRB 500-11: Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant 40 tonne capacity, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, 50 / 75mm compacted thickness with 3.3% bitumen but excluding cost of primer / tack cost with lead upto 1km including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5,With 60 / 70 grade bitumen, No. 176/ Item No. 21.11.2/ PWD SR 2013-14	cum	31.59	6646.32	Rupees six thousand six hundred forty six and paise thirty two only
5	KSRRB 500-7:Providing and applying Tack coat on the prepared black topped surfaces at 5kg per 10 sqm heating bitumen in boiler fitted with spray set (excluding clearing of road surface) including ost of all materials, labour, HOM of machinerles complete as per specifications MORTH chapter 5 with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	2445.00	17.93	Rupees seventeen and paise ninety three only
6	KSRRB M500-19 Providing and laying bituminous concrete 30-45mm compacted thickness (Grading II) with 6% bitumen 80/100 with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5.4 to 5.6% of mix and filler,transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No.500.9 complete in all respects as per specification. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	97.98	11284.92	Rupees eleven thousand two hundred eighty four and paise ninety two only
7	Lead for disposal of debris shall be payable at carage rates by Mechanical means including loading and unloading from 0.00 to 7.00 km average weight of earth 1.28 ton / cum with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	189.45	80.12	Rupees eighty and paise twelve only

Signature of the Contractor

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer,
Yelahanka Division,
BBMP, Bangalore.